

VILLAGE OF ONEKAMA

“On Beautiful Portage Lake”

Project Site One

8134 Second Street
Onekama, MI

The Salt Barn Building has approximately 2657 square feet of damaged 26 gauge corrugated metal roofing for removal and replacement, approximately 89 feet of steel rake / gable trim for removal and replacement, approximately 60 feet of ridge vent removed and replaced.

The Salt Barn Building has approximately 1466 square feet of damaged 26 gauge corrugated metal siding for removal and replacement and approximately 30 feet of metal outside corner post for removal and replacement. The project includes disposing of the damaged materials in a proper landfill.

The Garage Building has approximately 3542 square feet of damaged 26 gauge corrugated metal roofing for removal and replacement, approximately 89 feet of steel rake / gable trim for removal and replacement, approximately 80 feet of ridge vent removed and replaced.

The Garage Building has approximately 1726 square feet of damaged 26 gauge corrugated metal siding for removal and replacement and approximately 30 feet of metal outside corner post for removal and replacement. The project includes disposing of the damaged materials in a proper landfill.

The contractor is responsible for the condition of the work sites and shall control and clean up all trash and debris during the project. The sites will be clean when all work is complete. Trash generated during the project is the responsibility of the contractor.

No electricity, natural gas, water, sewer, or trash service is available at the work site.

For questions and approval of work please contact:

Village of Onekama
5283 Main Street
Onekama, Michigan
(231) 889-3171
clerk@villageofonekama.org

Village of Onekama
5283 Main Street – P. O. Box 477
Onekama, MI 49675-0477
(231) 889-3171
(231) 889-3423 (Fax)